

# HVAC&R



## FyreBOX™ Slab-Mount Bambino



The FyreBOX™ Slab-Mount Bambino is specifically manufactured for individual trades to simplify the job allowing installation of services before the erection of walls, providing predictable site costs and a reliable method of fire stopping, with independence from other contractor schedules.

A proudly Australian made passive fire penetration system made for trades.

**NCC compliant  
NCC 2022 ready!**

### Key Features



- Allows for multiple pipes, cables and drains in the one penetration
- Pipes can be installed, charged and tested before the walls are constructed
- Tested with typical A/C bundles (mixed services) and larger refrigerant lines
- Reduces penetration size
- Suitable for apartment entry and riser shaft penetrations
- Fully tested and compliant to AS1530.4-2014
- Training and support provided

### Approved Services

<b>Pair coil</b>	with PE or FR insulation
<b>Copper</b>	up to DN50 plus insulation up to 25mm thick
<b>Rockwool/ Nitrile Rubber</b>	(FR) and PE insulations tested
<b>Power/Data</b>	cables up to 25mm diameter
<b>PVC</b>	drain pipes up to 32mm

